



COSHOCTON COUNTY ENGINEER

(740) 622-2135 Fax: (740) 623-6512

Frederick J Wachtel, P.E., P.S.

Coshocton County Engineer's Office 2011 OPWC Bridge Program

Addendum Number 1 – June 30, 2011

Issue Date	Thursday, June 30, 2011
Issued By:	Andrew Jones, Deputy Engineer
Bid Date:	Wednesday, July 6, 2011
Bid Time:	9:00 a.m. Local Time

Addendum 1

1. Replace the original Bid Sheet with the attached Bid Sheet – Addendum 1 to correct the quantity of Type 2 guardrail posts and the off-deck posts. No other changes in the structure itself.

All other materials contained within the original bid documents remain the same and unchanged unless noted in subsequent addendums.

As per the bidding requirements, all addendums must be acknowledged in the Contracts Proposals on page Contract Form 1 (CF 1).

**Coshocton County Engineer - 2011
 UNIT PRICE CONTRACT
 ADDENDUM 1 – June 30, 2011
 Supply Pre-Stressed Concrete Box Beams as per plan**

INVITATION FOR BIDS: Please quote and insert complete prices for the items listed below.

SITE	ITEM DESCRIPTION	TOTAL AMOUNT
TR 191, BR-1	5 – pre-stressed concrete box beams 12” x 48” x 24.0’ - 6° right forward skew	
White Eyes Township	50’ – 6” deep beam guardrail w/tubular backup & 4 - 6x25x6’ galvanized guardrail posts with holes for mounting deep beam rail and tubular backup	
	8 – type 2 galvanized guardrail posts & all mounting hardware	
	Delivery to site and placement of beams	
	Total TR-191 BR-1	
TR 4, BR-10	5 – pre-stressed concrete box beams 21” x 48” x 44.0’ – no skew	
Pike Township	100’ – 6” deep beam guardrail w/tubular backup & 4- 6x25x6’ galvanized guardrail posts with holes for mounting deep beam rail and tubular backup	
	14 – type 2 galvanized guardrail posts & all mounting hardware	
	Delivery to site and placement of beams	
	Total TR-4, BR-10	
CR 297, BR-2	6 – pre-stressed concrete box beams 17” x 48” x 27.0’ – no skew	
Virginia Township	75’ – 6” deep beam guardrail w/tubular backup & 4- 6x25x6’ galvanized guardrail posts with holes for mounting deep beam rail and tubular backup	
	8 – type 2 galvanized guardrail posts & all mounting hardware	
	Delivery to site and placement of beams	
	Total CR-297, BR-2	

Continue to next page please

**Coshocton County Engineer - 2011
 UNIT PRICE CONTRACT
 ADDENDUM 1 – June 30, 2011
 Supply Pre-Stressed Concrete Box Beams as per plan page -2-**

CR 402, BR-1	6 – pre-stressed concrete box beams 17” x 48” x 40.0’ – 22° left forward skew	
Perry Township	100’ – 6” deep beam guardrail w/tubular backup & 4- 6x25x6’ galvanized guardrail posts with holes for mounting deep beam rail and tubular backup	
	12 – type 2 galvanized guardrail posts & all mounting hardware	
	Delivery to site and placement of beams	
	Total CR-402, BR-1	
	Combined total for TR-191, TR-4, CR-297 & CR-402	

TOTAL AMOUNT OF BID IN WORDS

COMPANY _____

ADDRESS _____

CITY _____ STATE _____ ZIP _____

QUOTED BY _____ TITLE _____

COMPANY TELEPHONE _____ FAX _____

APPROXIMATE DELIVERY DATE _____