



COSHOCTON COUNTY ENGINEER

(740) 622-2135 FAX: (740) 623-6512

Frederick T. Wachtel, P.E., P.S.

Coshocton County Engineer's Office 2020 OPWC County Resurfacing Program

Addendum Number 1 – July 10, 2020

Issue Date	Friday, July 10, 2020
Issued By:	Todd A. Coss P.E., P.S. Deputy Engineer
Bid Date:	Monday, July 13, 2020
Bid Time:	9:00 a.m. Local Time

Addendum 1

1. Replace sheet BF 15 with the attached BF 15a and BF 15b. A section of roadway was placed on N. 18th Street incorrectly and is actually Roscoe St. There are some quantity changes.
2. Replace sheet BF 23 with the attached revised BF 23 to account for the qty changes described in 1.

All other materials contained within the original bid documents remain the same and unchanged unless noted in subsequent addendums.

As per the bidding requirements, all addendums must be acknowledged in the Contracts Proposals on page Contract Form 1 (CF 1).

**Coshocton County Engineer
City of Coshocton**

Road: Roscoe St.
From: Hill
To: High
Length: 0.15 miles
Width: 21.0 feet
Courses: 1" leveling course
1" surface course
2" mill

ESTIMATED QUANTITIES				
REF. NO.	ITEM	DESCRIPTION	QUANTITY	
1	254	pavement planing	1839	sq. yds
2	407	tack coat @ 0.05 gal./sq. yd.	92	gal.
3	448, type 1	1" leveling course	103	tons
4	407	tack coat @ 0.05 gal./sq. yd.- intermed.	92	gal.
5	448, type 1	1" surface course	103	tons
16	614	maintaining traffic	lump	each

Coshocton County Engineer
City of Coshocton

Road: N. 18th
From: Hay
To: Chestnut
Length: 0.07 miles
Width: 20.0 feet
Courses: 1" leveling course
1" surface course
2" mill

ESTIMATED QUANTITIES				
REF. NO.	ITEM	DESCRIPTION	QUANTITY	
1	254	pavement planing	792	sq. yds
2	407	tack coat @ 0.05 gal./sq. yd.	40	gal.
3	448, type 1	1" leveling course	44	tons
4	407	tack coat @ 0.05 gal./sq. yd.- intermed.	40	gal.
5	448, type 1	1" surface course	44	tons
16	614	maintaining traffic	lump	each

Coshocoton County Engineer
2020 OPWC COUNTY RESURFACING PROGRAM

REF. NO.	ITEM NO.	APPROXIMATE UNIT QUANTITIES	ITEM DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	254	46,288 sq. yds	pavement planing		
2	407	5,890 gal.	tack coat @ 0.05 gal./sq. yd.		
3	448, type 1	6,541 tons	1" leveling course		
4	407	6,349 gal.	tack coat @ 0.05 gal./sq. yd.- intermed.		
5	448, type 1	6,541 tons	1" surface course		
6	448, type 1	766 tons	1-½" surface course		
7	407	440 gal.	tack coat for approaches		
8	448, type 1	480 tons	surface course for drive approaches		
9	604	3 each	manholes, adj. to grade		
10	638	1 each	valve box, adj. to grade		
11	617	1,531 tons	limestone or RAP		
12	202	318 each	RPM removal		
13	621	318 each	RPM		
14	643	3 miles	4" center line		
15	643	6 miles	4" edge lines		
16	614	lump sum	maintaining traffic	Lump Sum	
			TOTAL		

TOTAL AMOUNT OF BID IN WORDS

COMPANY	
ADDRESS	
CITY	STATE ZIP
SUBMITTED BY	
COMPANY	
TELEPHONE	FAX
EMAIL ADDRESS	
TAX ID NUMBER	

Acknowledgement of Published Addenda's:

☐ 1 ☐ 2 ☐ 3

Engineer's Estimate \$ 1,281,656.52