



COSHOCTON COUNTY ENGINEER

(740) 622-2135 FAX: (740) 623-6512

Frederick J. Wachtel, P.E., P.S.

Coshocton County Engineer's Office 2022 MVG Sealing, Motorpave, FDR Project

Addendum Number 1 – March 31, 2022

Issue Date	Thursday, March 31, 2022
Issued By:	Joshua D. Kempf, E.I., S.I. Assistant Engineer
Bid Date:	Wednesday, April 6, 2022
Bid Time:	9:00 a.m. Local Time

Addendum 1

1. Replace sheet BF 7, BF 8, BF 9, BF 10, BF 11, BF 12, BF 15, BF 23, BF 25, BF 26 with the attached with the attached corresponding sheets.

All other materials contained within the original bid documents remain the same and unchanged unless noted in subsequent addendums.

As per the bidding requirements, all addendums must be acknowledged in the Contracts Proposals on page Contract Form 1 (CF 1).

Coshocton County Engineer
2022 MVG SEALING, MOTORPAVE, FDR PROJECT
County Road 33

Road: County Road 33
From: CR 19
To: CR 319
Length: 3.28 miles
Width: 20.0 feet
Courses: Entire roadway will receive double chip seal of #57 limestone then #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	14,645 gallons
2	409	No. 8 limestone	482 tons
3	409	No. 57 limestone	674 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #57	17,343 gallons

Coshocton County Engineer
2022 MVG SEALING, MOTORPAVE, FDR PROJECT
County Road 80

Road: County Road 80
From: CR 3
To: SR 79
Length: 1.45 miles
Width: 20.0 feet
Courses: Entire roadway will receive double chip seal of #57 limestone then #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	6,486 gallons
2	409	No. 8 limestone	213 tons
3	409	No. 57 limestone	200 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #57	5,143 gallons

Coshocton County Engineer
2022 MVG SEALING, MOTORPAVE, FDR PROJECT
County Road 18

Road: County Road 18
From: CR 367
To: SR 541
Length: 2.71 miles
Width: 18.0 feet
Courses: Entire roadway will receive double chip seal of #57 limestone then #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	10,876 gallons
2	409	No. 8 limestone	358 tons
3	409	No. 57 limestone	501 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #57	12,880 gallons

Coshocton County Engineer
2022 MVG SEALING, MOTORPAVE, FDR PROJECT
County Road 3

Road: County Road 3

From: SR 60

To: SR 541

Length: 3.05 miles

Width: 19.0 feet

Courses: Entire roadway will receive double chip seal of #57 limestone then #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	12,901 gallons
2	409	No. 8 limestone	424 tons
3	409	No. 57 limestone	594 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #57	15,278 gallons

Coshocton County Engineer
2022 MVG SEALING, MOTORPAVE, FDR PROJECT
County Road 20

Road: County Road 20
From: FDR Locations from Previous Year
To:
Length: 1.53 miles
Width: 18.0 feet
Courses: Entire roadway will receive double chip seal of #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	6,151 gallons
2	409	No. 8 limestone	405 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #8	1,845 gallons

Coshocton County Engineer
2022 MVG SEALING, MOTORPAVE, FDR PROJECT
County Road 132

Road: County Road 132
From: TR 130
To: CL
Length: 1.21 miles
Width: 20.0 feet
Courses: Entire roadway will receive double chip seal of #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	5,379 gallons
2	409	No. 8 limestone	354 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #8	1,614 gallons

**Coshocton County Engineer
CR 319**

Road: CR 319

From: CR 49

To: CR 33

Length: 0.759 miles

Width: 13.0 feet

Reclamation: Full Depth Reclamation throughout with double seal of #8 Limestone

ESTIMATED QUANTITIES				
REF. NO.	ITEM	DESCRIPTION	QUANTITY	
10	1601	Full Depth Reclamation, 10"	5,800	sq. yards
11	304	Aggregate Base	650	tons
12	409	MC-3000 Seal, #8 (FDR)	2,200	gallons
13	409	No. 8 Limestone (FDR)	144	tons
15	614	Maintaining Traffic	lump	sum
16	409	MC-70 Seal, #8 (FDR)	1,737	gallons

**Coshocton County Engineer
 2022 MVG Reconstruction Project
 Tiverton Township Various Roads- Dust Mats**

Road: Tiverton Township Various Roads- Dust Mats

Roads	# of Mats	Length	Width	SY
Township Road 351	3	2,996	14	4,660
Township Road 351 Double 57's	1	157	12	419
Township Road 20	2	1,200	12	1,600
Township Road 20 Double 57's	1	200	12	533
Township Road 352 Double 57's	5	2,670	12	7,120
Township Road 136	4	1,472	12	1,963
Township Road 368	5	1,600	12	2,133
Township Road 368 Double 57's	1	450	12	1,200
Township Road 364	4	1,200	14	1,867
Community Center Double 57's	1			393

Length: 2.262 miles

Width: varied feet

Courses: Dust Mats will receive either single seal or double seal of #57 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #57	10,944 gallons
2	409	No. 57 limestone	383 tons
15	614	Maintaining Traffic	lump sum

Coshocton County Engineer
2022 MVG SEALING, MOTORPAVE, FDR PROJECT
White Eyes Township Various Roads-Dust Mats

Road: White Eyes Township Various Roads-Dust Mats

Roads	# of Mats	Length	Width	SY
Township Road 167	1	700	15	1,167
Township Road 170	3	2,010	14	3,127
Township Road 172	3	1,100	13	1,589
Township Road 173	1	400	14	622
Township Road 174	4	1,450	13	2,094
Township Road 177	1	300	10	333
Township Road 178	5	1,665	14	2,590
Township Road 191	4	1,300	14.5	2,094
Township Road 205	2	1,480	12	1,973

Length: 1.971 miles

Width: varied feet

Courses: Dust Mats will receive single chip seal of #57 limestone unless otherwise specified

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
4	409	No. 57 limestone	273 tons
15	409	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #57	7,016 gallons

**Coshocton County Engineer
 2022 MVG SEALING, MOTORPAVE, FDR PROJECT
 Bid Sheet**

REF. NO.	ITEM NO.	APPROXIMATE UNIT QUANTITIES		ITEM DESCRIPTION	UNIT PRICE	TOTAL PRICE
<i>Base Bid</i>						
1	409	108,803	gallons	MC 3000 (Seal, #8)		
2	409	3,690	tons	No. 8 Limestone (Seal, #8)		
3	409	10,944	gallons	MC 3000 (Seal, #57)		
4	409	2,625	tons	No. 57 Limestone (Seal, #57)		
5	254	182	sq. yds	Pavement Planing		
6	405	54,318	gallons	CMS-2 Mixing Liquid		
7	405	2,912	tons	No. 67 Limestone		
8	405	235	tons	No. 8 Gravel		
9	409	16,700	gallons	MC 3000 (MP)		
10	409	430	tons	No. 8 Limestone (MP)		
11	1601	5,800	sq. yds	Full Depth Reclamation, 10"		
12	304	650	tons	Aggregate Base		
13	409	2,200	gallons	MC 3000 (FDR)		
14	409	144	tons	No. 8 Limestone (FDR)		
15	614	lump sum	lump sum	Maintaining Traffic	Lump Sum	
16	409	61,119	gallons	MC 70 (Seal, #57)		
17	409	1,737	gallons	MC 70 (FDR)		
				TOTAL		

TOTAL AMOUNT OF BID IN WORDS

COMPANY

ADDRESS

CITY

STATE

ZIP

SUBMITTED BY

TITLE

COMPANY

TELEPHONE

FAX

TAX ID NUMBER

EMAIL ADDRESS

Acknowledgement of Published Addenda's:

1 2 3