



# COSHOCTON COUNTY ENGINEER

(740) 622-2135 FAX: (740) 623-6512

*Frederick J. Wachtel, P.E., P.S.*

## **Coshocton County Engineer's Office 2022 MVG Sealing, Motorpave, FDR Project**

### **Addendum Number 2 – April 1, 2022**

<b>Issue Date</b>	Friday, April 1, 2022
<b>Issued By:</b>	Joshua D. Kempf, E.I., S.I. Assistant Engineer
<b>Bid Date:</b>	Wednesday, April 6, 2022
<b>Bid Time:</b>	9:00 a.m. Local Time

### **Addendum 1**

1. Replace sheet BF 11, BF 12, BF 13, BF 14, BF 26 with the attached with the attached corresponding sheets.

All other materials contained within the original bid documents remain the same and unchanged unless noted in subsequent addendums.

As per the bidding requirements, all addendums must be acknowledged in the Contracts Proposals on page Contract Form 1 (CF 1).

**Coshocton County Engineer**  
**2022 MVG SEALING, MOTORPAVE, FDR PROJECT**  
**County Road 20**

**Road:** County Road 20  
**From:** FDR Locations from Previous Year  
**To:**  
**Length:** 1.53 miles  
**Width:** 18.0 feet  
**Courses:** Entire roadway will receive double chip seal of #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	6,151 gallons
2	409	No. 8 limestone	405 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #8	4,856 gallons

**Coshocton County Engineer**  
**2022 MVG SEALING, MOTORPAVE, FDR PROJECT**  
**County Road 132**

**Road:** County Road 132  
**From:** TR 130  
**To:** CL  
**Length:** 1.21 miles  
**Width:** 20.0 feet  
**Courses:** Entire roadway will receive double chip seal of #8 limestone

ESTIMATED QUANTITIES			
REF. NO.	ITEM	DESCRIPTION	QUANTITY
1	409	MC-3000 Seal, #8	5,379 gallons
2	409	No. 8 limestone	354 tons
15	614	Maintaining Traffic	lump sum
16	409	MC-70 Seal, #8	4,247 gallons

**Coshocton County Engineer  
 County Road 24**

**Road:** County Road 24  
**From:** TR 45  
**To:** SR 60  
**Length:** 1.47 Miles  
**Width:** 22.0 Feet  
**Courses:** CMS-2 1.4 GAL/SY  
 No. 67 150 #/SY  
 No. 8 gravel 12 #/SY  
 MC 3000 0.43 GAL/SY  
 No. 8 limestone 22 #/SY

ESTIMATED QUANTITIES				
REF. NO.	ITEM	DESCRIPTION	QUANTITY	
5	254	Pavement Planing	98	SY
6	405	CMS-2 Mixing Liquid	26558	GAL
7	405	No. 67 Limestone	1422	TON
8	405	No. 8 Gravel	115	TON
9	409	MC-3000 (MP)	9105	GAL
10	409	No. 8 Limestone (MP)	210	TON
15	614	Maintaining Traffic	1	LS

**Coshocton County Engineer  
 County Road 343**

**Road:** County Road 19  
**From:** TR 312  
**To:** CR 19  
**Length:** 1.78 Miles  
**Width:** 19.0 Feet  
**Courses:** CMS-2 1.4 GAL/SY  
 No. 67 150 #/SY  
 No. 8 gravel 12 #/SY  
 MC 3000 0.43 GAL/SY  
 No. 8 limestone 22 #/SY

ESTIMATED QUANTITIES				
REF. NO.	ITEM	DESCRIPTION	QUANTITY	
5	254	Pavement Planing	84	SY
6	405	CMS-2 Mixing Liquid	27760	GAL
7	405	No. 67 Limestone	1490	TON
8	405	No. 8 Gravel	120	TON
9	409	MC-3000 (MP)	9520	GAL
10	409	No. 8 Limestone (MP)	220	TON
15	614	Maintaining Traffic	1	LS

**Coshocton County Engineer**  
**2022 MVG SEALING, MOTORPAVE, FDR PROJECT**  
**Bid Sheet**

REF. NO.	ITEM NO.	APPROXIMATE UNIT QUANTITIES	ITEM DESCRIPTION	UNIT PRICE	TOTAL PRICE
<b>Base Bid</b>					
1	409	108,803 gallons	MC 3000 (Seal, #8)		
2	409	3,690 tons	No. 8 Limestone (Seal, #8)		
3	409	10,944 gallons	MC 3000 (Seal, #57)		
4	409	2,625 tons	No. 57 Limestone (Seal, #57)		
5	254	182 sq. yds	Pavement Planing		
6	405	54,318 gallons	CMS-2 Mixing Liquid		
7	405	2,912 tons	No. 67 Limestone		
8	405	235 tons	No. 8 Gravel		
9	409	18,625 gallons	MC 3000 (MP)		
10	409	430 tons	No. 8 Limestone (MP)		
11	1601	5,800 sq. yds	Full Depth Reclamation, 10"		
12	304	650 tons	Aggregate Base		
13	409	2,200 gallons	MC 3000 (FDR)		
14	409	144 tons	No. 8 Limestone (FDR)		
15	614	lump sum	Maintaining Traffic	Lump Sum	
16	409	66,762 gallons	MC 70 (Seal, #57)		
17	409	1,737 gallons	MC 70 (FDR)		
			<b>TOTAL</b>		

TOTAL AMOUNT OF BID IN WORDS

COMPANY

ADDRESS

CITY

STATE

ZIP

SUBMITTED BY

COMPANY

TELEPHONE

FAX

TITLE

TAX ID NUMBER

EMAIL ADDRESS

Acknowledgement of Published Addenda's:

1  2  3