#### COSHOCTON COUNTY ENGINEER



(740) 622-2135 FAX: (740) 623-6512 Frederick T. Wachtel, P.S., P.S.

### Coshocton County Engineer's Office 2024 MVG Sealing, FDR Project

Addendum Number 1 – April 16, 2024

**Issue Date** Tuesday, April 16, 2024

**Issued By:** Joshua D. Kempf, P.E., S.I.

Deputy Engineer

Bid Date: Monday, April 29, 2024

**Bid Time:** 9:00 a.m. Local Time

#### Addendum 1

1. Replace sheet BF 12 & BF 18 with the attached corresponding sheet.

All other materials contained within the original bid documents remain the same and unchanged unless noted in subsequent addendums.

As per the bidding requirements, all addendums must be acknowledged in the Contracts Proposals on page Contract Form 1 (CF 1).

# Coshocton County Engineer 2024 MVG SEALING, FDR PROJECT County Road 410

Road: County Road 410

**From:** CR 149

To: End of Pavement

Length: 1.45 miles

Width: 20.0 feet

**Courses:** Entire roadway will receive single seal of #8 limestone

ESTIMATED QUANTITIES							
REF. NO	D. ITEM	DESCRIPTION	QUANTITY				
1	409	MC-3000 Seal, #8	6,792 gallons				
2	409	No. 8 limestone	212 tons				
15	614	Maintaining Traffic	lump sum				

## Coshocton County Engineer 2024 MVG SEALING, FDR PROJECT Newcastle Township Various Roads- Dust Mats

**Road:** Newcastle Township Various Roads- Dust Mats

Roads	# of Mats	Length	Width	SY
Township Road 113	5	1,650	16	2,933
Township Road 111	2	2,730	13	3,943
Township Road 41A	2	1,400	12	1,867
Township Road 41	1	600	12	1,600
Township Road 444	1	1,400	12	1,867
Township Road 53	4	2,050	13	2,961
Township Road 422	2	600	13	867

Length: 1.975 miles

Width: varied feet

Courses: Dust Mats will receive 10" FDR

ESTIMATED QUANTITIES						
REF. NO	. ITEM	DESCRIPTION	QUANTITY			
1	1601	Full Depth Reclamation, 10"	16,038 SY			
5	614	Maintaining Traffic	lump sum			