


COSHOCTON COUNTY ENGINEER

(740) 622-2135 FAX: (740) 623-6512

Frederick T. Wachtel, P.E., P.S.

Coshocton County Engineer's Office 2016 OPWC County Resurfacing Program

Addendum Number 1 – May 20, 2016

Issue Date	Friday, May 20, 2016
Issued By:	 Andrew Jones, Deputy Engineer
Bid Date:	Wednesday, May 25, 2016
Bid Time:	9:30 a.m. Local Time

Addendum 1

1. Add two (2) roadways from Jackson Township (TR-78 and TR 301) as part of this project.
2. Replace Bid Sheet (BF-27) to include additional items and modify quantities as necessary.
3. Increase the Engineer's Estimate to \$1,170,000.00.

All other materials contained within the original bid documents remain the same and unchanged unless noted in subsequent addendums.

As per the bidding requirements, all addendums must be acknowledged in the Contracts Proposals on page Contract Form 1 (CF 1).

**Coshocton County Engineer
County Resurfacing Program 2016
Bid Sheet - Addendum 1 - May 20, 2016**

REF. NO.	ITEM NO.	APPROXIMATE UNIT QUANTITIES		ITEM DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	Supp 101	67,870	sq. yds.	reclaimed stabilized base, 10"		
2	251	457	sq. yds.	partial depth repair 6"		
3	254	12,292	sq. yds.	pavement planing		
4	407	2,220	gal.	tack coat @ 0.05 gal./sq. yd.		
5	407	15	gal.	tack coat for approaches		
6	407	1,920	gal.	tack coat @ 0.05 gal./sq. yd.- intermed.		
7	448, type 1	2,152	tons	leveling course		
8	448, type 1	2,152	tons	1" surface course		
9	448, type 1	495	tons	1½" surface course		
10	448, type 1	30	tons	extra for drive approaches		
11	448, type 2	9,460	tons	2.5" intermediate course		
12	448, type 2	50	tons	extra for drive approaches		
13	604	16	each	manholes, adj. to grade		
14	638	10	each	valve box, adj. to grade		
15	617	1,165	tons	limestone or RAP		
16	202	648	each	RPM removal		
17	643	20	feet	stop bars		
18	614	lump sum	lump sum	maintaining traffic	Lump Sum	
19	301	1235	tons	3" bituminous asphalt base		
				TOTAL		

TOTAL AMOUNT OF BID IN WORDS

COMPANY

ADDRESS

CITY

STATE

ZIP

SUBMITTED BY

TITLE

COMPANY

TELEPHONE

FAX

TAX ID NUMBER

EMAIL ADDRESS

Acknowledgement of Published Addenda's:

☒ 1☐ 2☐ 3

Engineer's Estimate \$1,170,000

Coshocoton County Engineer
Bid Sheet - Addendum 1 - May 20, 2016
Township Road 78

Road: Township Road 78
From: Township Road 55
To: end of pavement
Length: 1250 feet
Width: 17 feet
Courses: 3.0" Asphalt Bituminous Base

ESTIMATED QUANTITIES				
REF. NO.	ITEM	DESCRIPTION	QUANTITY	
3	254	Pavement Planing	30	sq. yds
19	301	3" Asphalt Bituminous Base	395	tons
18	614	Maintaining Traffic	lump sum	

Coshocoton County Engineer
Bid Sheet - Addendum 1 - May 20, 2016
Township Road 301

Road: Township Road 301
From: Township Road 55
To: end of pavement
Length: 2825 feet
Width: 16 feet
Courses: 3.0" Asphalt Bituminous Base

ESTIMATED QUANTITIES				
REF. NO.	ITEM	DESCRIPTION	QUANTITY	
3	254	Pavement Planing	30	sq. yds.
19	301	3" Asphalt Bituminous Base	840	tons
18	614	Maintaining Traffic	lump sum	